

DESIGNER NOTE:
DESIGNER TO CONFIRM WITH
PERMITS WHICH BANNER IS
TO BE USED ON A PROJECT
SPECIFIC BASIS.

ARCHITECTURAL GENERAL KEY NOTES:	
G1.	HIGH POINT OF CONCRETE - SLOPE TOWARD TRENCH.
G2.	4" WIDE PAINTED OUTLINE FOR EQUIPMENT ON FLOOR. PAINT TRA.F.F.C. YELLOW.
G3.	TRENCH DRAIN.
G4.	FLOOR DRAIN - SLOPE FLOOR 1/4" FOR A 2'-0" DIA AREA CENTERED ON DRAIN. SEE PLUMBING DRAWINGS. TOP OF DRAIN COVER SHALL BE FLUSH W/ ADJ. FLOOR FINISH MATERIAL.
G5.	INTERIOR RAIN WATER LEADER.
G6.	2" x 4" PEGBOARD (BY OTHERS).
G7.	REQUIRED CLEAR ACCESS AREA AT DOOR.
G8.	CONTINUOUS LIMESTONE COLORED SIKAFLEX 1A SEALANT FOR TILE TRANSITION TO FLOOR.
G9.	STORAGE CABINET (BY OTHERS).
G10.	WASHER BOX FOR ICE MAKER - SEE PLUMBING DWGS.
G11.	2" x 2" PLASTIC CORNER GUARD - INSTALL PER MANUFACTURERS INSTRUCTIONS (REFER TO REQUIRED VENDOR LIST). BUTT BASE TO CORNER GUARD. SEE DETAIL 11/A12.0.
G12.	2" x 2" ALUMINUM CORNER GUARD (NATIONAL ACCOUNT MILLWORK VENDOR). WRAP JAMBS AND HEAD WHEN OCCURRING AT CASSED OPENINGS - SEE DETAIL 10/A12.0.
G13.	WALL SURFACE MOUNTED CART BUMPER GUARD +2'-6" TO CENTERLINE FENCE BLOCKING - SEE DETAIL 7/A12.0 (SEE REQUIRED VENDOR LIST).
G14.	FLOOR MOUNTED CART BUMPER - POLISHED CHROME (SEE REQUIRED VENDOR LIST).
G15.	WALL SURFACE MOUNTED CART BUMPER GUARD ABOVE AND SURFACE MOUNTED CRASH RAIL BELOW. (SEE REQUIRED VENDOR LIST). SEE DETAIL 7/A12.0.
G16.	4" x 4" WALL MOUNTED TACKBOARD PROVIDED AND INSTALLED BY OTHERS.
G17.	4" x 6" WALL MOUNTED TACKBOARD PROVIDED AND INSTALLED BY OTHERS.
G18.	DECORATIVE FENCE AND GATE (NATIONAL ACCOUNT MILLWORK VENDOR).
G19.	CHEMICAL MIXING SYSTEM (BY OTHERS).
G20.	REFRIGERATOR (BY OTHERS).
G21.	MILLWORK (NATIONAL ACCOUNT MILLWORK VENDOR).
G22.	VENDING MACHINES (BY OTHERS).
G23.	TAG MACHINE (BY OTHERS).
G24.	ADOPTION FUTURE / CAGES (NATIONAL ACCOUNT MILLWORK VENDOR).
G25.	PET TRAINING WALL FIXTURE / RAILING (NATIONAL ACCOUNT MILLWORK VENDOR).
G26.	SOAP DISPENSER.
G27.	SOAP DISPENSER. ATTACH TO RIGHT HAND CORNER OF MIRROR OVER SINK.
G28.	HAND SANITIZER.
G29.	PAPER TOWEL DISPENSER. SEE BARRIER-FREE ACCESSIBILITY NOTES ON SHEET A0.2.
G30.	TOILET PAPER DISPENSER. SEE BARRIER-FREE ACCESSIBILITY NOTES ON SHEET A0.2.
G31.	TOILET SEAT COVER DISPENSER. SEE BARRIER-FREE ACCESSIBILITY NOTES ON SHEET A0.2.
G32.	SANITARY NAPKIN DISPOSAL. SEE BARRIER-FREE ACCESSIBILITY NOTES ON SHEET A0.2.
G33.	MIRROR - CAULK PERIMETER TO WALL WITH CLEAR SILICONE.
G34.	STAINLESS STEEL, 1-1/4" DIA. GRAB BAR. INSTALL HORIZ. WALL BLOCKING FOR SOLID MOUNTING. TYP. SEE BARRIER-FREE ACCESSIBILITY NOTES ON SHEET A0.2.
G35.	KOALA BEAR KARE BABY CHANGER MANUFACTURED BY KOALA CORPORATION, HORIZONTAL TYPE, MOUNTED AT 2'-9" A.F.F. SEE BARRIER-FREE ACCESSIBILITY NOTES ON SHEET A0.2.
G36.	OVERHEAD BRACED METAL TOILET PARTITION AND URINAL CLOSURES TO CEILING STOP. PROVIDE WALL BUMPERS AT BARRIER-FREE STALL DOORS.
G37.	3/8" GALVANIZED EYEBOLT EPOXY ANCHORED 2 1/2" (MIN) IN FLOOR, 4" OFF THE FACE OF WALL UNLESS NOTED OTHERWISE. TOP OF EYEBOLT TO BE 5" A.F.F.
G38.	INSULATED DRAIN AND HOT WATER LINE TYPICAL. SEE BARRIER-FREE ACCESSIBILITY NOTES ON SHEET A0.2.
G39.	5'-0" BARRIER-FREE TURNING DIAMETER.
G40.	30" x 48" CLEAR ACCESS. SEE BARRIER-FREE ACCESSIBILITY NOTES ON SHEET A0.2.
G41.	LOW/HIGH DRINKING TATION. MOUNT PER BARRIER-FREE REQUIREMENTS - PROVIDE 2x6 BLOCKING AS REQUIRED. APPLY CLEAR CAULK TO ALL SEAMS.
G42.	CLOTHES HOOK AND BUMPER. SEE BARRIER-FREE ACCESSIBILITY NOTES ON SHEET A0.2.
G43.	WALLBOARD, PAINT - SEE FINISH SCHEDULE.
G44.	FRP PANEL, WALL COVERING SYSTEM. INSTALL PER MANUFACTURERS DETAILS & INSTRUCTIONS.
G45.	12" x 12" CERAMIC TILE. CONTINUE THE CERAMIC TILE BEHIND ALL FIXTURES.
G46.	6" x 24" CERAMIC TILE. CONTINUE THE CERAMIC TILE BEHIND ALL FIXTURES.
G47.	PROVIDE CONTINUOUS LIMESTONE COLORED SIKAFLEX 1A AT JOINT OF PLYWOOD WALL FINISH TO FLOOR.
G48.	4" RUBBER BASE.
G49.	4" RUBBER BASE ON FRP. FRP INSTALLED BY NATIONAL ACCOUNT MILLWORK VENDOR. RUBBER BASE INSTALLED BY GC.
G50.	COMPOSITE BASE - TANGENT RESIN BOARD SUPPLIED AND INSTALLED BY NATIONAL ACCOUNT MILLWORK VENDOR.
G51.	RECESSED ELECTRICAL PANEL - SEE ELECTRICAL DRAWINGS.
G52.	SALES AREA LIGHT FIXTURE IN FOREGROUND.
G53.	UNFINISHED WALLBOARD, TAPE MUD & SAND.
G54.	FIRE ALARM PULL STATION.
G55.	FIRE ALARM ANNUNCIATOR PANEL.
G56.	SECURITY ALARM KEYPAD.
G57.	DATA OUTLET.
G58.	DUPLEX RECEPTACLE.
G59.	QUADPLEX RECEPTACLE.
G60.	DECORATIVE GRAPHICS LEDGE (BY OTHERS). GC TO PROVIDE 24" HIGH (CONTINUOUS) - 1/2" PLYWOOD BLOCKING IN STUD WALL FOR DECORATIVE LEDGE ATTACHMENT (LEDGE BY OTHERS).
G61.	LIGHT SWITCH.
G62.	JUNCTION BOX.
G63.	DORNBELL / BUZZER FOR SALON CUTTING AREA. BUTTON IN MILLWORK PROVIDED BY NATIONAL ACCOUNT VENDOR. INSTALL BY E.C.
G64.	VOLUME CONTROL.
G65.	BUZZER.
G66.	REMOTE TEMPERATURE SENSOR.
G67.	REMOTE HUMIDITY/TEMPERATURE SENSOR.
G68.	THERMOSTAT.
G69.	DISCONNECT FOR WATER HEATER.
G70.	RECIRCULATING PUMP SWITCH.
G71.	RECIRCULATING PUMP. SEE PLUMBING.

ARCHITECTURAL BARRIER-FREE KEY NOTES (CANADA):	
G200.	INSTALL WASHROOM SIGNAGE. SEE A6.0 HARDWARE SCHEDULE, HARDWARE GROUP 10.
G201.	INSTALL UNIVERSAL WASHROOM SIGNAGE. SEE A6.0 HARDWARE SCHEDULE, HARDWARE GROUP 12.
G202.	EMERGENCY CALL PUSH BUTTON WITH SIGNAGE ABOVE BUTTON.
G203.	BARRIER-FREE DOOR PUSH BUTTONS.
G204.	OUTLINE OF FUTURE ADULT SIZE CHANGE TABLE. PROVIDE 3/4" PLYWOOD BLOCKING IN WALL 8'-0" WIDE x 8'-0" HIGH.
G205.	OCCUPANCY SENSOR FOR SECONDARY CONTROL OF FIXTURES MOUNTED ON WALL BEHIND TANKS @84" A.F.F..
G206.	EMERGENCY CALL SYSTEM CHIME/STROBE, CENTER OVER DOOR ON BOTH SIDES.
G207.	DOOR OPERATOR LOCK BUTTON.

DESIGNER NOTE:
CHANGE SIGNAGE IS REQUIRED BY LOCAL JURISDICTION AND/OR WASHROOM PLAN LAYOUT.

DESIGNER NOTE:
ON A PROJECT SPECIFIC BASIS WHEN A KEYNOTE IS NOT USED AND NOT OF NOTE IN CASE OF A CHANGE TO THE PROJECT FOR ANY REASON, IT IS NOT TO BE USED IN THE PROJECT DRAWINGS. THE DRAWING SHALL BE USED TO INCLUDE THE PROJECT AND ANY NEW PROJECT SPECIFIC NOTES TO END OF LIST.

[illegible]