

PART I – GENERAL**WORK SPECIFIED HEREIN**

All labor, materials, equipment and services necessary to furnish and install all roof hatches as indicated or specified.

SUBMITTALS

Unless otherwise noted, the contractor shall prepare all shop drawings, product literature, etc. only as required to properly coordinate and construct the project.

Review of submittals by the Professional of Record is limited to specific shop drawings as called for in this Project Manual.

SUBSTITUTIONS

In accordance with Section 01600.

PART II – PRODUCTS**MATERIALS**

This specification is based on roof hatches as manufactured by those listed within the Material and Product Schedule shown on the Drawings.

Covers shall be galvanized steel, prime painted, 1.9 mm (14 gauge) with 75 mm (3") beaded flange neatly welded. Insulation shall be glass fiber, 25 mm (1") in thickness, fully covered and protected by a galvanized steel, prime painted, 0.72 mm (22 gauge) metal liner. Curb shall be 400 mm (16") high of galvanized steel, prime painted, 1.9 mm (14 gauge), formed with a 89 mm (3-1/2") flange with holes provided for securing to roof deck. Equip curb with an integral metal cap flashing of the same gauge and material as the curb, full welded at the corners for absolute weather tightness. Insulation on exterior of the curb shall be 25 mm (1") thick rigid fiberboard.

PART III – EXECUTION**INSTALLATION**

Install roof hatches at location indicated, fastening securely to deck through curb flange.

END OF SECTION

This Page Intentionally Left Blank.