

PART I – GENERAL

WORK SPECIFIED HEREIN

- All labor, material, equipment and services necessary to provide wall and corner guards as indicated or specified. **This is a Required Vendor.**

SUBMITTALS

- Unless otherwise noted, the contractor shall prepare all shop drawings, product literature, etc. only as required to properly coordinate and construct the project.
- Review of submittals by the Professional of Record is limited to specific shop drawings as called for in the Project Manual.

SUBSTITUTIONS

- In accordance with Section 01600.

COORDINATION

- Coordinate with all other trades whose work relates to items specified herein for placing of all required backing and furring, to ensure proper locations.
- Verify all dimensions shown on drawings by taking field measurement; proper fit and attachment of all parts is required.

DELIVERY, STORAGE AND HANDLING

- Deliver and store all items specified herein in dry, protected areas. Keep free of corrosion or other damage. Replace any damaged items at no cost to the Owner.

PART II – PRODUCTS

MATERIALS

- Corner guard shall be: 50 mm x 50 mm (2"x2") Surface Mounted with top cap and bottom caps.
- G.C to provide 20ga strapping as required at all wall bumpers.
- Crash rail shall be surface mounted with end caps
- Refer to Materials and Product Schedule for Additional Information.

PART III – EXECUTION

INSTALLATION

- Install all items per manufacturer's published instructions and approved installation drawings.

END OF SECTION

This Page Intentionally Left Blank.