OPENING SOON BANNER ORDER FORM

THIS BANNER PACKAGE CONSISTS OF (1) "OPENING SOON" BANNER REQUIRED BY PETSMART

- 13 OZ BANNER MATERIAL
- DIGITAL PRINT
- GROMMETS, HEMS & WIND HOLES

petsmart.com

JOB SITE:

PETSMART STORE # _____
NAME _____
STREET _____
CITY _____
ST. _____ ZIP _____

CONTRACTOR: (PAID BY)

COMPANY _____
STREET _____
CITY _____
ST. _____ ZIP _____
PHONE _____

SHIP TO:

CONTACT PERSON _____
NAME _____
STREET _____
CITY _____
ST. _____ ZIP _____
PHONE _____

PAYMENT METHOD ☐ CHECK ☐ CREDIT CARD ☐ VISA ☐ MASTERCARD

PURCHASERS NAME _____ (EXACTLY AS IT APPEARS ON CARD, IF APPLICABLE)

SIGNATURE _____

DATE _____

COST $ 431.00 (INCLUDES 1 BANNER, SHIPPING AND HANDLING)

LOCAL SALES TAX $ _____ (PLEASE CALCULATE TAX)

TOTAL ENCLOSED $ _____

THE BANNER PACKAGE WILL BE SHIPPED FED EX GROUND SHIPPING WITHIN 3-5 BUSINESS DAYS. (REQUIRED FOR PROCESSING AND PRODUCTION) ALL BANNER ORDERS MUST BE PRE-PAID.

COMPLETE THIS FORM FOR EACH SEPARATE PACKAGE. ATTACH A CHECK FOR FULL PRICE OR EMAIL FORM FOR CREDIT CARD PAYMENT TO:

image national signs ...bringing your image to light!

Image National, Inc.
16365 Star Road
Nampa, Idaho USA 83687-8415
tel: 208.345.4020 · imagenational.com

Rory Paulson (208) 287-1923 rory.paulson@imagenational.com
Beth Ludden (986) 999-2123 beth.ludden@imagenational.com

Image National • (208) 345-4020 • imagenational.com

OPENING SOON BANNER ORDER FORM

THIS BANNER PACKAGE CONSISTS OF (1) "OPENING SOON" BANNER REQUIRED BY PETSMART

- 13 OZ BANNER MATERIAL
- DIGITAL PRINT
- GROMMETS, HEMS & WIND HOLES

JOB SITE:

PETSMART STORE # _____
NAME _____
STREET _____
CITY _____
ST. _____ ZIP _____

CONTRACTOR: (PAID BY)

COMPANY _____
STREET _____
CITY _____
ST. _____ ZIP _____
PHONE _____

SHIP TO:

CONTACT PERSON _____
NAME _____
STREET _____
CITY _____
ST. _____ ZIP _____
PHONE _____

PAYMENT METHOD ☐ CHECK ☐ CREDIT CARD ☐ VISA ☐ MASTERCARD

PURCHASERS NAME _____ (EXACTLY AS IT APPEARS ON CARD, IF APPLICABLE)

SIGNATURE _____

DATE _____

COST $ _____ (INCLUDES 1 BANNER, SHIPPING AND HANDLING)

LOCAL SALES TAX $ _____ (PLEASE CALCULATE TAX)

TOTAL ENCLOSED $ _____

THE BANNER PACKAGE WILL BE SHIPPED FED EX GROUND SHIPPING WITHIN 3-5 BUSINESS DAYS. (REQUIRED FOR PROCESSING AND PRODUCTION) ALL BANNER ORDERS MUST BE PRE-PAID.

COMPLETE THIS FORM FOR EACH SEPARATE PACKAGE. ATTACH A CHECK FOR FULL PRICE OR EMAIL FORM FOR CREDIT CARD PAYMENT TO:

image national signs ...bringing your image to light!

Image National, Inc.
16365 Star Road
Nampa, Idaho USA 83687-8415
tel: 208.345.4020 · imagenational.com

Rory Paulson (208) 287-1923 rory.paulson@imagenational.com
Beth Ludden (986) 999-2123 beth.ludden@imagenational.com

Image National • (208) 345-4020 • imagenational.com

DESIGNER NOTE:
DESIGNER TO CONFIRM WITH PETSMART WHICH BANNER IS TO BE USED ON A PROJECT SPECIFIC BASIS.

GENERAL CONTRACTOR MILESTONE REQUIREMENTS: (PER LEASE)

CONSTRUCTION SCHEDULE AND COST BREAKDOWN

WITHIN 10 WORKING DAYS OF EXECUTION AND DELIVERY OF THE CONTRACT FOR CONSTRUCTION AND BEFORE THE FIRST PARTIAL PAYMENT IS MADE, THE GENERAL CONTRACTOR SHALL DELIVER TO THE OWNER AND PETSMART A CONSTRUCTION PROGRESS SCHEDULE VIA ONLINE POSTING, SHOWING, AT MINIMUM, THE PROPOSED DATES OF COMMENCEMENT AND COMPLETION OF EACH OF THE VARIOUS SUBDIVISIONS OF THE WORK REQUIRED UNDER THE CONSTRUCTION DOCUMENTS AS WELL AS CERTAIN MILESTONE DATES INCLUDING 50%, MILLWORK AND AQUARIUM INSTALLATION, PUNCH LIST AND TURNOVER (SETUP), WHICH ARE DESCRIBED BELOW.

PHONE LINE / SYSTEM INSTALLATION REQUIREMENTS.

LANDLORD WITH GENERAL CONTRACTOR'S ASSISTANCE SHALL COMPLETE THE FOLLOWING:

- LANDLORD TO CONFIRM BUILDING ENTRANCE AT THE OUTSET OF BUILDING WORK.
- LANDLORD TO ORDER / RESERVE BROADBAND CABLE SERVICE FOR PETSMART IN SITE SPECIFIC UTILITY PACKAGE. ORDER IS TO BE PLACED NO LATER THAN THE OUTSET OF BUILDING WORK.
- LANDLORD / CONTRACTOR TO INSTALL 3" CONDUIT TO PETSMART PHONE BACKBOARD WITH PULL STRING TO D-MARK / PHONE PEDESTAL / PULL BOX FOR ROUTING OF CABLE….TWO WEEKS PRIOR TO MILLWORK DATE.
- LANDLORD / CONTRACTOR SHALL INSTALL AND PAINT PHONE BACKBOARD (MATCH ADJACENT WALL COLOR) AND INSTALL GROUND WIRE / POWER OUTLET FOR PHONE CABLE INSTALLATION….TWO WEEKS PRIOR TO MILLWORK DATE.
- LANDLORD / CONTRACTOR SHALL IDENTIFY AND RELAY LOCATION TO PETSMART OF TELEPHONE DEMARC FOR SPACE (EXTERIOR OF BUILDING / SHARED UTILITY ROOM). ADDITIONALLY, THEY SHALL PROVIDE APPROXIMATE DISTANCE OF CABLE RUN TO PETSMART INTERIOR PHONE BACKBOARD…TWO WEEKS PRIOR TO MILLWORK.
- LANDLORD / CONTRACTOR ARE TO ENSURE PERMANENT POWER IS IN PLACE NO LATER THAN ONE WEEK PRIOR TO MILLWORK INSTALLATION (WEEK OF PHONE LINE CABLING).
  NOTE: PERMANENT POWER WILL BE REQUIRED PRIOR TO THIS TO COMPLETE INTERIOR FINISH WORK.
- LANDLORD / CONTRACTOR ARE TO ENSURE CABLE IS PULLED IN AND PUNCHED DOWN (DIAL TONE IS OPERATIONAL)…ONE WEEK PRIOR TO MILLWORK INSTALLATION.
- LANDLORD / CONTRACTOR TO ENSURE ALL ELECTRICAL OUTLETS ARE WORKING AND MISC. PHONE J-BOXES ARE INSTALLED AT MILLWORK INSTALLATION DATE.
- LANDLORD / CONTRACTOR TO INSTALL POWER POLES IMMEDIATELY AFTER REGISTER LOCATIONS ARE SET DURING MILLWORK INSTALLATION…FOR COMPLETION OF FOLLOW ON WORK.

50% OBSERVATION (NINE WEEKS PRIOR TO BUILDING TURNOVER /SET-UP)

ARCHITECT OF RECORD AND PETSMART REPRESENTATIVE MUST CONDUCT A COURTESY "50% OBSERVATION" TO VERIFY PROJECT IS ON SCHEDULE AND IS BEING CONSTRUCTED IN ACCORDANCE WITH PLANS AND SPECIFICATIONS. TIME AND DATE MUST BE COORDINATED WITH PETSMART CONSTRUCTION MANAGER A MINIMUM OF THREE WEEKS PRIOR TO REQUESTED OBSERVATION DATE.
AT MINIMUM, GENERAL CONTRACTOR MUST CAUSE ALL TRADES TO MEET THE FOLLOWING REQUIREMENTS.

- ROOFING MUST BE COMPLETE AND BUILDING "DRIED IN."
- ALL HVAC UNITS AND EXHAUST FANS TO BE SET ON ROOF CURBS.
- THE ELECTRICAL SERVICE EQUIPMENT MUST BE SET IN PLACE.
- ALL INTERIOR METAL STUD WALL FRAMING MUST BE COMPLETED.
- ALL "IN WALL" MECHANICAL / PLUMBING / ELECTRICAL ROUGH-INS MUST BE COMPLETED.
- ALL STUD WALLS MUST HAVE DRYWALL INSTALLED ON ONE SIDE.
- ALL BLOCKING FOR WALL MOUNTED FIXTURES, EQUIPMENT, ETC. MUST BE INSTALLED INSIDE WALLS PER THE BLOCKING SCHEDULES.
- ALL WALL INSULATION MUST BE INSTALLED PER SPECIFICATIONS.
- ALL IN-WALL WATER LINES MUST BE INSULATED PER SPECIFICATIONS.
- THE UNDERSIDE OF THE METAL DECK AND ROOF FRAMING MUST BE PAINTED.
- SALES AREA AND RECEIVING AREA LIGHT FIXTURES MUST BE INSTALLED.
- ALL EXTERIOR DOORS MUST BE INSTALLED AND THE BUILDING MUST BE SECURED.
- THE EXTERIOR CANOPY MUST BE STARTED.
- THE "COMING SOON BANNER MUST BE INSTALLED ON THE EXTERIOR OF THE BUILDING.
- A 4'X6' DRYWALL FINISH SAMPLE MUST BE PREPARED AND READY FOR SUBMITTAL ON SITE.
- INTERIOR BUILDING TEMPERATURE MUST BE HELD TO A HEATING TEMPERATURE OF NOT LESS THAN 65 °F AND A COOLING TEMPERATURE OF NOT MORE THAN 75 °F.
- TEMPORARY LIGHTING MUST BE INSTALLED IN ALL AREAS OF SPACE SUFFICIENT TO CONDUCT THE OBSERVATION.

MILLWORK AND AQUARIUM DELIVERY (FOUR WEEKS PRIOR TO BUILDING TURNOVER)

GENERAL CONTRACTOR MUST CAUSE SUBCONTRACTORS TO BE APPROXIMATELY 95% COMPLETE PRIOR TO MILLWORK AND AQUARIUM DELIVERY. MILLWORK PACKAGE IS CONTRACTED AND COORDINATED BY GENERAL CONTRACTOR THROUGH PETSMART'S REQUIRED VENDOR. MILLWORK PACKAGE WILL ARRIVE ON A MONDAY. AQUARIUM PACKAGE IS COORDINATED BY GENERAL CONTRACTOR THROUGH PETSMART'S VENDOR. AQUARIUM EQUIPMENT WILL ARRIVE ON TUESDAY 2 WEEKS AFTER MILLWORK. COORDINATE VENDOR WITH PETSMART CONSTRUCTION MANAGER.
GENERAL CONTRACTOR MUST CAUSE THE FOLLOWING ITEMS TO OCCUR PRIOR TO MILLWORK AND AQUARIUM DELIVERY...

- ALL FLOOR FINISHES 100% COMPLETED
- ALL PAINTING (FINISH COAT) 100% COMPLETED.
- MINIMUM 75% OF THE SALES FLOOR MUST BE CLEAR INCLUDING THE AREA SURROUNDING THE CHECKSTANDS AND THE AREA AROUND THE FISH EQUIPMENT. THIS IS WHERE THE MILLWORK AND AQUARIUM INSTALLERS WILL WORK FROM DURING THE INSTALL.
- ALL EXTERIOR DOORS AND LOCKS MUST BE INSTALLED AND FUNCTIONING.
- ENTIRE BUILDING MUST HAVE CLEAR ACCESS INTO AND OUT OF THE BUILDING AND INTO AND OUT OF ALL ROOMS.
- ALL EXTERIOR ELEVATIONS RECEIVING SIGNAGE MUST BE READY FOR INSTALL.
- FORKLIFT, BATTERY CHARGER, AND PALLET JACKS WILL BE DELIVERED TO STORE THE THURSDAY (CONFIRMED BY G.C.) BEFORE DELIVERY OF MILLWORK AND AQUARIUMS. **CHARGER TO BE HOOKED UP AND PLUGGED INTO FORKLIFT IMMEDIATELY SO IT IS FULLY CHARGED WHEN THE MILLWORK AND AQUARIUMS ARRIVE MONDAY MORNING.**
- HAVE ALL STAINLESS STEEL SINKS ON SITE SO MILLWORK INSTALLER CAN CUT IN.
- UTILITY INFORMATION MUST BE POSTED ON WEB PAGE UNDER PROJECT INFO AREA
- ALL PERMANENT UTILITIES MUST BE COMPLETED, CONNECTED, AND SERVICING THE BUILDING.
- THE ENTIRE SPACE MUST HAVE CONDITIONED AIR. THE HVAC SYSTEM MUST HAVE BEEN STARTED UP AND SHOULD BE FUNCTIONING. (DOES NOT NEED TO BE RUNNING THROUGH THE EMS SYSTEM AT THIS TIME.)
- THE LIGHTING SYSTEM MUST BE INSTALLED 100% COMPLETE AND FUNCTIONING.
- ALL CEILING GRID AND TILE MUST BE INSTALLED WITH FUNCTIONING LIGHT FIXTURES AND HVAC DROPS INSTALLED.
- PHONE LINES FROM THE LOCAL EXCHANGE CARRIER MUST HAVE BEEN PULLED INTO THE BUILDING AND LANDED AT THE TELEPHONE DEMARC ON THE TELEPHONE BACKBOARD NEAR THE POWERWALL (IPC) ELECTRICAL SERVICE EQUIPMENT.
- THE ENTIRE BUILDING MUST BE BROOM CLEAN.
- CERTAIN ADDITIONAL ITEMS WILL BE REQUIRED BY THE GENERAL CONTRACTOR DURING THE MILLWORK AND AQUARIUM INSTALLATION PHASE. AT MINIMUM, THE FOLLOWING ITEMS MUST BE PROVIDED BY THE GENERAL CONTRACTOR
- THE MILLWORK INSTALLER SHOULD INSTALL THE CHECK STANDS AS ONE OF THEIR FIRST TASKS. ONCE THE CHECK STANDS HAVE BEEN SET IN PLACE THE ELECTRICAL CONTRACTOR SHOULD IMMEDIATELY INSTALL THE POWER / DATA.
- THE FINAL ELECTRICAL AND PLUMBING CONNECTIONS FOR THE AQUARIUM SYSTEM SHOULD BE MADE IMMEDIATELY FOLLOWING THE SYSTEMS INSTALLATION BUT NO LATER THAN THURSDAY OF THE INSTALLATION WEEK.

PUNCH LIST

THE ARCHITECT OF RECORD WILL PERFORM THE FINAL PUNCH LIST ALONG WITH THE PETSMART CONSTRUCTION MANAGER APPROXIMATELY TEN BUSINESS DAYS AFTER GENERAL CONTRACTOR'S RECEIPT OF THE MILLWORK PACKAGE. GENERAL CONTRACTOR SHALL COORDINATE EXACT DATE AND TIME WITH PETSMART CONSTRUCTION MANAGER. AT MINIMUM, THE FOLLOWING CRITERIA MUST BE MET PRIOR TO BUILDING PUNCH.

- ALL LIGHTING, HVAC, EMS, PLUMBING AND LIFE SAFETY SYSTEMS MUST BE 100% FUNCTIONAL.
- SUPERINTENDENT WILL HAVE COMPLETED THEIR OWN "PRE-PUNCH" AND REPORTED RESULTS TO PETSMART CONSTRUCTION MANAGER.
- ALL PAINT TOUCH-UPS MUST BE COMPLETE.
- BUILDING FINAL CLEANING MUST BE COMPLETE.
- PARKING LOT MUST BE 100% COMPLETE INCLUDING ALL STRIPING, SIGNAGE AND CART CORRALS.
- ANY LANDSCAPING MUST BE COMPLETED PER PLANS.
- ALL CONSTRUCTION TOOLS, EQUIPMENT AND MATERIALS MUST BE REMOVED.
- ATTIC STOCK MUST BE READY FOR VERIFICATION BY PETSMART CONSTRUCTION MANAGER. SEE SECTION 1700 FOR FULL LIST OF REQUIRED PARTS.
- PROVIDE A PHOTO OF THE FIRE SPRINKLER HYDRAULIC CALCULATION SYSTEM PLACARD INSTALLED AT THE FIRE RISER TO PETSMART CM.

BUILDING TURNOVER (SETUP)

BUILDING TURNOVER (ALSO KNOWN AS THE "SET-UP DATE") WILL OCCUR FOUR WEEKS AFTER RECEIPT OF THE MILLWORK PACKAGE. GENERAL CONTRACTOR WILL BE SUBSTANTIALLY COMPLETE WITH THE "PUNCH ITEMS" PRIOR TO THIS DATE. PETSMART'S FIXTURE VENDOR WILL ARRIVE ON MONDAY AT 8:00 AM, LOCAL TIME. GENERAL CONTRACTOR WILL MEET THE FIXTURE VENDOR ON SITE TO TURN THE KEYS OVER TO THE FIXTURE INSTALLATION FOREMAN. AT MINIMUM, THE FOLLOWING CRITERIA MUST BE MET PRIOR TO THE SETUP DATE.

- GOVERNMENTAL PERMISSION TO FIXTURE MUST BE OBTAINED.
- GOVERNMENTAL PERMISSION TO INTERVIEW POTENTIAL EMPLOYEES MUST BE GRANTED ONE WEEK PRIOR TO THE "SET-UP DATE."
- ANY CLEANING REQUIRED BY PUNCH LIST REPAIRS MUST BE COMPLETED.
- GENERAL CONTRACTOR WILL COORDINATE WITH THE FIXTURE INSTALLER AND THE ELECTRICIAN FOR FIXTURES REQUIRING POWER DROPS APPROXIMATELY 4 DAYS AFTER FIXTURES START.

DESIGNER NOTE:
DESIGNED TO REVISE TO 67" F. 2017 ICC-ANSI 117.1 IS TO BE USED

ARCHITECTURAL G1 GENERAL KEY NOTES:

G1. HIGH POINT OF CONCRETE - SLOPE TOWARD TRENCH.
G2. 4" WIDE PAINTED OUTLINE FOR EQUIPMENT ON FLOOR. PAINT TRAFFIC YELLOW.
G3. TRENCH DRAIN.
G4. FLOOR DRAIN - SLOPE FLOOR 1/4" FOR A 2'-0" DIA. AREA CENTERED ON DRAIN. SEE PLUMBING DRAWINGS. TOP OF DRAIN COVER TO FINISH FLUSH W/ TOP OF ADJ. FLOOR FINISH MATERIAL.
G5. INTERIOR RAIN WATER LEADER.
G6. 2x4 PEGBOARD (BY OTHERS).
G7. REQUIRED CLEAR ACCESS AREA AT DOOR.
G8. CONTINUOUS LIMESTONE COLORED SIKAFLEX SEALANT FOR TILE TRANSITION TO FLOOR.
G9. STORAGE CABINET (BY OTHERS).
G10. WASHER BOX FOR ICE MAKER - SEE PLUMBING DWGS.
G11. 2" x 2" PLASTIC CORNER GUARD - INSTALL PER MANUFACTURERS INSTRUCTIONS (REFER TO REQUIRED VENDOR LIST). BUTT WALL BASE TO CORNER GUARD. SEE DETAIL 11/A12.0.
G12. 2" x 2" ALUMINUM CORNER GUARD. WRAP JAMBS AND HEAD WHEN OCCURRING AT CASED OPENINGS - SEE DETAIL 12/A12.0. (FURNISHED AND INSTALLED BY NATIONAL ACCOUNT MILLWORK VENDOR)
G13. WALL SURFACE MOUNTED CART BUMPER +2'-6" TO CENTERLINE - PROVIDE BLOCKING - SEE DETAIL 7/A12.0 (SEE REQUIRED VENDOR LIST).
G14. FLOOR MOUNTED CART BUMPER - POLISHED CHROME. (SEE REQUIRED VENDOR LIST.)
G15. WALL SURFACE MOUNTED BUMPER GUARD ABOVE AND SURFACE MOUNTED CRASH RAIL BELOW. (SEE REQUIRED VENDOR LIST). SEE DETAIL 7/A12.0.
G16. 4' x 4' WALL MOUNTED TACKBOARD PROVIDED AND INSTALLED BY OTHERS.
G17. 4' x 6' WALL MOUNTED TACKBOARD PROVIDED AND INSTALLED BY OTHERS.
G18. DECORATIVE FENCE AND GATE (NATIONAL ACCOUNT MILLWORK VENDOR).
G19. CHEMICAL MIXING STATION (BY OTHERS).
G20. REFRIGERATOR (BY OTHERS).
G21. MILLWORK (NATIONAL ACCOUNT MILLWORK VENDOR)
G22. VENDING MACHINES (BY OTHERS).
G23. TAG MACHINE (BY OTHERS).
G24. ADOPTION FIXTURE / CAGES (NATIONAL ACCOUNT MILLWORK VENDOR).
G25. PET TRAINING FIXTURE (NATIONAL ACCOUNT MILLWORK VENDOR).
G26. SOAP DISPENSER.
G27. SOAP DISPENSER. ATTACH TO RIGHT HAND CORNER OF MIRROR OVER SINK.
G28. HAND SANITIZER.
G29. PAPER TOWEL DISPENSER. SEE ADA ACCESSIBILITY NOTES ON SHEET A0.2.
G30. TOILET PAPER DISPENSER. SEE ADA ACCESSIBILITY NOTES ON SHEET A0.2.
G31. TOILET SEAT COVER DISPENSER. SEE ADA ACCESSIBILITY NOTES ON SHEET A0.2.
G32. SANITARY NAPKIN DISPOSAL. SEE ADA ACCESSIBILITY NOTES ON SHEET A0.2.
G33. MIRROR - CAULK PERIMETER TO WALL WITH CLEAR SILICONE.
G34. STAINLESS STEEL, 1-1/4" DIA. GRAB BAR. INSTALL HORIZ. WALL BLOCKING FOR SOLID MOUNTING, TYP. SEE ADA ACCESSIBILITY NOTES ON SHEET A0.2.
G35. KOALA BEAR KARE BABY CHANGER MANUFACTURED BY KOALA CORPORATION, HORIZONTAL TYPE, MOUNTED AT ACCESSIBLE HEIGHT. SEE ADA ACCESSIBILITY NOTES ON SHEET A0.2.
G36. OVERHEAD BRACED METAL TOILET PARTITION AND URINAL SCREEN WITH FLOOR TO CEILING POST. PROVIDE WALL BUMPERS AT ADA STALL DOORS.
G37. 3/8" GALVAVANIZED EYEBOLT EPOXY ANCHORED 2 1/2" (MIN) IN FLOOR 4" OFF THE FACE OF WALL UNLESS NOTED OTHERWISE. TOP OF EYEBOLT TO BE 3" AFF.
G38. INSULATED DRAIN AND HOT WATER LINE TYP. SEE ADA ACCESSIBILITY NOTES ON SHEET A0.2.
G39. 5'-0" A.D.A. TURNING DIAMETER.
G40. 30" x 48" CLEAR ACCESS. SEE ADA ACCESSIBILITY NOTES ON SHEET A0.2.
G41. LOW/HIGH DRINKING FOUNTAIN, MOUNT PER A.D.A. REQUIREMENTS - PROVIDE 2x6 BLOCKING AS REQUIRED. CAULK REAR OF DRINKING FOUNTAIN TO FRP W/ CLEAR SILICONE SEALANT.
G42. CLOTHES HOOK AND BUMPER. SEE ADA ACCESSIBILITY NOTES ON SHEET A0.2.
G43. WALLBOARD, PAINT - SEE FINISH SCHEDULE.
G44. FRP WALL COVERING SYSTEM. INSTALL PER MFR. DETAILS & INSTRUCTIONS.
G45. 12" X 12" CERAMIC TILE, CONTINUE THE CERAMIC TILE BEHIND ALL FIXTURES.
G46. 6" X 24" CERAMIC TILE, CONTINUE THE CERAMIC TILE BEHIND ALL FIXTURES.
G47. PROVIDE CONTINUOUS LIMESTONE COLORED SIKAFLEX 1A AT JOINT OF PLYWOOD WALL FINISH AND FLOOR.
G48. 4" RUBBER BASE.
G49. 4" RUBBER BASE ON FRP. FRP INSTALLED BY NATIONAL ACCOUNT MILLWORK VENDOR, RUBBER BASE INSTALLED BY GC.
G50. COMPOSITE BASE - TANGENT RESIN BOARD SUPPLIED AND INSTALLED BY NATIONAL ACCOUNT MILLWORK VENDOR.
G51. RECESSED ELECTRICAL PANEL - SEE ELECTRICAL DRAWINGS.
G52. SALES AREA LIGHT FIXTURE IN FOREGROUND.
G53. UNFINISHED WALLBOARD, TAPE, MUD & SAND.
G54. FIRE ALARM PULL STATION.
G55. FIRE ALARM ANNUNCIATOR PANEL.
G56. SECURITY ALARM KEYPAD.
G57. DATA OUTLET.
G58. DUPLEX RECEPTACLE.
G59. QUADPLEX RECEPTACLE.
G60. DECORATIVE GRAPHICS LEDGE (BY OTHERS). GC TO PROVIDE 24" HIGH CONTINUOUS 3/4" PLYWOOD BLOCKING IN STUD WALL FOR DECORATIVE LEDGE ATTACHMENT.
G61. LIGHT SWITCH.
G62. JUNCTION BOX.
G63. DOORBELL / BUZZER FOR SALON CUTTING AREA. BUTTON IN MILLWORK PROVIDED BY NATIONAL ACCOUNT MILLWORK VENDOR, INSTALL BY E.C..
G64. VOLUME CONTROL.
G65. BUZZER.
G66. REMOTE TEMPERATURE SENSOR.
G67. REMOTE HUMIDITY/TEMPERATURE SENSOR.
G68. THERMOSTAT.
G69. DISCONNECT FOR WATER HEATER.
G70. RECIRCULATING PUMP SWITCH.
G71. RECIRCULATING PUMP - SEE PLUMBING DWGS.

DESIGNER NOTE:
DESIGNER TO CONFIRM WITH PETSMART WHICH BANNER IS TO BE USED ON A PROJECT SPECIFIC BASIS.

ARCHITECTURAL G1 GENERAL KEY NOTES:

G72. WATER HEATER.
G73. BATTERY CHARGER - MOUNT AT 3'-0" A.F.F. W/ PROVIDED HARDWARE.
G74. MOP SINK - SEE DETAIL 3/A12.0.
G75. MOP HANGER W/ CLIPS AT +4'-6" A.F.F. PROVIDE 2X BLOCKING AS REQUIRED.
G76. ENERGY MANAGEMENT SYSTEM NATIONAL ACCOUNT VENDOR PUSH BUTTON OVERRIDE.
G77. 3/4" FIRE RETARDANT TREATED CDX PLYWOOD TO 16'-0" A.F.F. INSTALLED HORIZONTALLY WITH STAGGERED JOINTS. SCREW FASTENED INTO METAL STUDS. UNFINISHED, CONTINUOUS CAULK AT END OF RUN. PROVIDE 5/8" GYP. BD. ABOVE 16'-0" TO ROOF DECK.
G78. G.C. SHALL WRAP EXPOSED COLUMN WITH 18 GA., #4 BRUSHED STAINLESS STEEL TO 48" A.F.F. (TYP. OF ALL EXPOSED COLUMNS) CAULK ALL SEAMS W/ CLEAR SILICONE SEALANT. SEE DETAIL 2/A12.0.
G79. 4" DIA. INTERIOR CONCRETE FILLED PIPE BOLLARD. SEE DETAIL 4/A12.0.
G80. 48" HIGH STEEL TRACK GUARD BY LOADING DOCK EQUIPMENT VENDOR. SECURE TO FLOOR PER MANUFACTURERS RECOMMENDATIONS.
G81. 6" PVC TUBE W/ END CAPS FOR CONSTRUCTION DOCUMENT STORAGE. G.C. TO SUPPLY AND INSTALL. G.C. TO PLACE FULL SET OF RECORD DRAWINGS IN TUBE AT COMPLETION OF PROJECT. SUPPLIED AND INSTALLED BY G.C./E.C. SEE DETAIL 6/A12.0.
G82. ATTACH IPC POWER PANELS TO WALL PER MFR. INSTRUCTIONS. ATTACH XFMR SHELF TO VENDOR PROVIDED BRACKET. SECURE BRACKET TO WALL PER WALL TYPE DETAIL W13.
G83. MAXIMUM SPACE ALLOWED FOR FIRE PROTECTION & DOMESTIC WATER.
G84. SELF CONTAINED PORTABLE EYEWASH BY OTHERS.
G85. FIRE RISER/SPRINKLER SYSTEM SHUTOFF VALVE.
G86. MUSIC EQUIPMENT BOARD BY OTHERS.
G87. MECHANICAL GRILLE, FACTORY FINISH WHITE (DO NOT PAINT) - SEE MECHANICAL PLANS. LOCATED AS HIGH AS POSSIBLE UNLESS OTHERWISE NOTED.
G88. TIMER SWITCHES.
G89. GYPSUM BOARD CONTROL JOINT AT THIS LOCATION. INSTALL PER SPECIFICATIONS.
G90. CONCRETE BLOCK WALL
G91. SINGLEPLEX RECEPTACLE.
G92. PHONE BOARD.
G93. EXPOSED PIPING - DO NOT PAINT.
G94. PLUMBING VALVES (SURFACE MOUNTED).
G95. CONCRETE CURB INTEGRAL WITH SLAB ON GRADE.
G96. WATER HEATER EXPANSION TANK, WALL MOUNTED.
G97. TILE TO EXTEND TO EDGE OF TRAINING FIXTURE. INSTALL TILE AFTER TRAINING FIXTURE IS ON SITE AND EXACT LOCATION CAN BE FIELD VERIFIED.
G98. FRAMED MIRROR - SUPPLIED AND INSTALLED BY NATIONAL ACCOUNT MILLWORK VENDOR - SEE INTERIOR ELEVATIONS.
G99. CAGES (BY OTHERS).
G100. BENCHES - FURNISHED AND INSTALLED BY OTHERS.
G101. LEASH BAR - FURNISHED AND INSTALLED BY NATIONAL ACCOUNT MILLWORK VENDOR.
G102. SHELF FOR BATHING BUNKER INSTALLED BY NATIONAL ACCOUNT MILLWORK VENDOR FOR PETSMART.
G103. 5" x 16" STAINLESS STEEL SHELF FOR BATHROOM AND DRINKING FOUNTAIN. SEE MATERIAL AND PRODUCT SCHEDULE ON SHEET F2.0. PROVIDE BLOCKING IN WALL. SEE ADA ACCESSIBILITY NOTES ON SHEET A0.2.
G104. MASTER BLASTER HANGING CLIPS TO BE FURNISHED AND INSTALLED BY NATIONAL ACCOUNT MILLWORK VENDOR.
G105. OUTLINE OF 3/4" PLYWOOD BLOCKING, SEE BLOCKING SCHEDULE.
G106. LIGHTING IN RECEIVING AREA MOUNTED ABOVE THE BOTTOM CHORD OF STEEL JOISTS.
G107. FORKLIFT TURNING RADIUS, 12' DIAMETER.
G108. SOLAR WINDOW SHADES - SEE MATERIAL & PRODUCT SCHEDULE. INSTALLED FROM TOP OF WINDOW TO TOP OF HORIZONTAL MULLION 7'-6" A.F.F. AT AUTO SLIDER TRANSOM AND FROM TOP OF WINDOW TO SILL AT FULL HEIGHT WINDOWS - SEE DETAIL 13/A6.1.
G109. LOCKERS PROVIDED AND INSTALLED BY OTHERS.
G110. BIRD DETERRENT SHOCK TRACK SYSTEM CHARGER BY NIXALITE OF AMERICA, INC. SUPPLIED BY NATIONAL ACCOUNT LIGHTING VENDOR (SEE MATERIAL & PRODUCT SCHEDULE). INSTALL PER MANUFACTURERS RECOMMENDATIONS. MOUNT TOP AT 7'-4" A.F.F.
G111. MECHANICAL DUCT DROP, PAINT TO MATCH C-1. HOLD TIGHT TO BOTTOM OF ROOF STRUCTURE - SEE MECHANICAL DRAWINGS.
G112. AREA TO REMAIN CLEAR FOR NATIONAL ACCOUNT DECOR GRAPHICS PROVIDED AND INSTALLED BY OTHERS.
G113. ROOM SIGNAGE - SEE HARDWARE SCHEDULE.
G114. DOOR STOP - SEE HARDWARE SCHEDULE.
G115. EMERGENCY BATTERY UNIT - SEE ELECTRICAL DRAWINGS.
G116. CAULK TOP AND VERTICAL EXPOSED EDGES OF CERAMIC TILE WITH LIMESTONE COLORED SIKAFLEX 1A.
G117. ROOF ACCESS LADDER - PAINT YELLOW - SEE 1/A12.0.
G118. WALL MOUNTED LIGHT FIXTURE - SEE ELECT. DWGS.
G119. VERTICAL STORING HYDRAULIC PIT LEVELER.
G120. DOCK LEVELER CONTROL BOX.
G121. PROPORTIONER SOAP DISPENSER
G122. DOCK LEVELER PIT STEEL ANGLE - PAINT YELLOW
G123. STAINLESS STEEL SHELF FOR FISH PREP, PROVIDED BY NATIONAL ACCOUNT VENDOR. SEE MATERIAL AND PRODUCT SCHEDULE ON SHEET F2.0. PROVIDE BLOCKING IN WALL.
G124. FIRE SAFETY PLAN.
G125. INSTALL SIGNAGE "THIS DOOR TO REMAIN UNLOCKED DURING BUSINESS HOURS" ABOVE BOTH INTERIOR AND EXTERIOR SLIDERS.
G126. 3" PVC. NIPPLE THROUGH WALL. TOP OF NIPPLE/PIPE INSTALLED IN LINE WITH AND 1" BELOW BOTTOM CHORD OF BAR JOIST. PAINT TO MATCH WALL COLOR.
G127. PROVIDE 4" CONCRETE HOUSEKEEPING PAD FOR EQUIPMENT.
G128. MILLWORK SPACER PANEL (NATIONAL ACCOUNT MILLWORK VENDOR)
G129. SURFACE MOUNTED CART BUMPER +6" AND +2'-6" TO CENTERLINE (FURNISHED AND INSTALLED BY NATIONAL ACCOUNT MILLWORK VENDOR)

DESIGNER NOTE:
ON A PROJECT SPECIFIC BASIS, AS NEEDED
- CASE WORKS PROVIDED AND INSTALLED BY
- OTHERS. TO BE COORDINATED WITH THE
INTERNATIONAL SIGN OF ACCESSIBILITY

ARCHITECTURAL X1 EXTERIOR KEY NOTES:

X1. SIDEWALK
X2. SIDEWALK CONTROL JOINT - 1/4" MAX. TOOLED JOINT. LOCATE WHERE INDICATED ON PLAN (6'-0" O.C. MAX.)
X3. SIDEWALK EXPANSION JOINT. LOCATE WHERE INDICATED ON PLAN (20'-0" O.C. MAX.) - SEE STRUCT. DWGS.
X4. 1/2" EXPANSION JOINT WITH TRAFFIC SEALANT
X5. ADA ACCESSIBLE RAMP, PROVIDE ADA COMPLIANT TACTILE WARNING.
X6. CONCRETE CURB (DO NOT PAINT) - SEE DETAIL 6/A10.0.
X7. FLUSH CONDITION AT DOOR, PROVIDE 2% MAX. SLOPE AWAY FROM DOOR. SEE ADA ACCESSIBILITY NOTES ON SHEET A0.2.
X8. SURFACE MOUNT OUTLET WITH WATERPROOF COVER @ 60" A.F.F. - NO EXPOSED CONDUIT
X9. ASH/TRASH CAN BY G.C. - SEE MATERIAL & PRODUCT SCHEDULE ON SHEET F2.0.
X10. RECESSED HOSE BIBB AT 28" A.F.G.
X11. PUSH BUTTON FOR BUZZER SURFACE MOUNTED AT BRAKE METAL WRAPPED COLUMN AT STOREFRONT (NO EXPOSED CONDUIT) - SEE ELECTRICAL DWGS.
X12. 6" DIA. CONCRETE FILLED PIPE BOLLARD - SEE DETAIL 5/A12.0.
X13. CANOPY - PREFINISHED STEEL PLATE AWNING / EYEBROW - SEE WALL SECTIONS ON SHEET A10.0 AND STRUCT. DWGS.
X14. GAS METER
X15. ELECTRIC METER
X16. ELECTRICAL TRANSFORMER ON CONCRETE PAD
X17. DUMPSTER PAD - SEE STRUCT. DWGS.
X18. TRASH CONTAINERS BY OTHERS. VERIFY REQUIRED CLEARANCE W/ TRASH SERVICE PROVIDER.
X19. TRUCK DOCK SLAB - SEE STRUCT. DWGS