

PART I – GENERAL**WORK SPECIFIED HEREIN**

- All labor, materials, equipment and services necessary to furnish and install all wall base and related items as indicated or specified.

SUBMITTALS

- Unless otherwise noted, the contractor shall prepare all shop drawings, product literature, etc. only as required to properly coordinate and construct the project.
- Review of submittals by the Professional of Record is limited to specific shop drawings as called for in the Project Manual.
- Shop drawings for review by the Professional of Record are not required for this section.

QUALITY ASSURANCE

- Installer Qualification: All base products shall be installed by a trained installer and approved by the product manufacturer.

PRODUCT DELIVERY, STORAGE AND HANDLING

- Store all materials off the ground under watertight cover and away from sweating walls and other damp surfaces until ready for use. All rooms, subfloors, tiles and adhesives shall be maintained at a minimum temperature of 70° F. for at least 48 hours before commencing work. Temperature shall be maintained during installation and for at least 48 hours after completion.

PROTECTION

- Protect finished work installed by other trades prior to work under this section. Any work damaged by workmen of this trade shall be replaced without cost to the Owner.

EXTRA MATERIAL

- Provide 20 feet continuous roll of each color type used.

PART II – PRODUCTS**MATERIALS**

Refer to Materials and Product Schedule for additional information.

Rubber Base:

- Molded rubber coved base (top set) conforming to FS SS-W-40, Type II, 4" high x 1/8" thick. (G.C. to provide and install base at Owner supplied cabinetry and at Fish Aquarium racks.) Base shall be from roll stock in minimum 20'-0" lengths - same dye lot.

Adhesives and Primers:

- Adhesives shall be the "preferred choice" type and brand recommended by manufacturer for each of the various conditions and materials.
- Primers for use for all the various conditions and materials shall be as recommended by manufacturer of each specific material and for each specific application.

PART III – EXECUTION**PREPARATION**

Inspect all surfaces to receive base and report all defects that will affect the installation. The work under this section includes smoothing of walls with underlayment as required to receive cove base. Concrete surfaces to receive base shall be dry, free of paint and oil, and swept clean before work commences.

BASE INSTALLATION

After preparation of wall surface, apply adhesive to back of base leaving top 1/4" free of adhesive. Press base firmly against the walls sliding horizontally into place, making sure toe is tight to the floor and against the wall. Roll the entire surface of the base with a hand roller, and press the top of the base against the wall with a straight edge. Remove excess adhesive immediately.

END OF SECTION

This Page Intentionally Left Blank.