

SECTION 10800: TOILET AND BATH ACCESSORIES

PART I – GENERAL

WORK SPECIFIED HEREIN

- All labor, materials, equipment and services necessary to furnish and install all toilet accessories as indicated or specified.

QUALITY ASSURANCE

- This Specification is based on products as listed within the Materials and Product Schedule shown on the drawings, unless otherwise noted.

SUBMITTALS

- Unless otherwise noted, the contractor shall prepare all shop drawings, product literature, etc. only as required to properly coordinate and construct the project.
- Review of submittals by the Professional of Record is limited to specific shop drawings as called for in the Project Manual.
- Shop drawings for review by the Professional of Record are not required for this section.

GENERAL REQUIREMENTS

- Review Drawings for locations of toilet accessories and verify dimensional requirements for recessed units. Coordinate location of blocking and built-in anchorage devices.
- Notify PETSMART Representative of any conflicts with accessory locations and partition dimensions or piping interference.
- Use concealed fastening wherever possible.
- Provide anchors, bolts and other necessary fasteners, and attach accessories securely to walls and partitions in locations as shown or directed.
- Provide products of the same manufacturer for each type of accessory unit and for units exposed in the same areas, wherever possible.
- Stamped names or labels on exposed faces of units will not be permitted, except where otherwise specified.
- All dispensers are supplied to PETSMART at no cost. The contractor is only charged for delivery.

PART II – PRODUCTS

TOILET ACCESSORIES

- Provide shipping, coordination, storage, blocking, fasteners/anchors and installation of all toilet accessories shown and those listed on the Materials and Product Schedule shown on the Drawings.

PART III – EXECUTION

EXAMINATION

- Verification of Conditions: Examine the areas and conditions under which the work of this Section will be performed. Correct conditions

detrimental to timely and proper completion of the Work. Do not proceed until unsatisfactory conditions are corrected.

INSTALLATION

- *General:* Install the work of this Section in accordance with the manufacturer's written instructions and recommendations, anchoring components firmly into position for long life under hard use.
- *Coordination:* Coordinate as required with other trades to assure proper and adequate provision in the work of those trades for interface with the work of this Section. Coordinate schedules for installation of the orderly progress of the total construction sequence.
- Deviation of site conditions contrary to approved shop drawings shall be called to the attention of the PETSMART Representative.
- Install all toilet accessories at locations indicated in strict accordance with manufacturer's printed instructions.
- Install concealed mounting devices and fasteners fabricated of the same material as the accessories or of galvanized steel.
- Install exposed mounting devices and fasteners finished to match the accessories.
- Provide theft-resistant fasteners for all accessory mountings.
- Secure toilet room accessories to adjacent walls and partitions in accordance with the manufacturer's instructions for each item and each type of substrate construction.
- Install grab bars in accordance with manufacturer's printed instructions at locations indicated. Install connectors or support angles between studs. Attachment of support angles to studs must be sufficient to withstand a horizontal pull of 300 pounds. Accurately position connector assemblies and tighten to the support angles before wall finish is applied. After wall surface is finished, secure concealed mounting plate to connector assembly using stainless steel machine screws furnished by the manufacturer. Where grab bars installed on toilet compartments make through-bolted connection with specified anchors.
- Provide full perimeter caulking at mirror, lavatory and w/c to wall and floor

CLEANING

- Upon completion of this portion of the work, promptly clean exposed portions and remove traces of dirt, grease and foreign materials.

PROTECTION

- Upon completion of the installation, visually check exposed surfaces of the work of this Section, and touch up scratches and abrasives to be completely invisible.

END OF SECTION

This Page Intentionally Left Blank.