

PART I – GENERAL**GENERAL**

Furnish and install circuits, feeders, and outlets, as shown on the drawings completely connect and leave store fixtures, checkout stands and equipment as indicated on the drawings, in proper operating condition. A general description of such work follows; however, any omission of details will not relieve the contractor of the responsibility of completely connecting the various items. It shall be the duty of the contractor to familiarize himself with details involved by actual examination of equipment and fixtures. Cases and checkout standard are subject to some relocations; all dimensions and locations indicated shall be verified with representative of PETSMART and fixtures or equipment supplier before actual installation. Type of junction box outlet to be provided for each piece of equipment and case shall be determined by the type of fixtures or cases to be installed. Verify location of all electrical requirements with PETSMART immediately prior to rough-in. Connect wiring between adjacent cases, store fixtures, equipment of all items in each line-up, etc., for complete wiring.

SUBMITTALS

- Unless otherwise noted, the contractor shall prepare all shop drawings, product literature, etc. only as required to properly coordinate and construct the project.
- Review of submittals by the Professional of Record is limited to specific shop drawings as called for in the Project Manual.
- Shop drawings for review by the Professional of Record are not required for this section.

PART II – PRODUCTS**CHECKOUT STANDS**

- Furnish and install the following wiring, outlets, circuitry, and connections for each checkout stand. Provide facilities as specified herein for NCR Cash Register Terminal System. Completely connect checkout stands that are to be installed and provide blanked outlets.

MISCELLANEOUS EQUIPMENT

- The contractor shall rough-in for and make final connection to all miscellaneous equipment requiring electrical connections as shown and called for on the drawings. All work shall be done in accordance with approved shop drawings furnished by the equipment supplier. Where rough-in only is called for, sufficient pigtails shall be left in the outlet boxes to facilitate extension to the equipment. Ends of conductors shall be properly taped and boxes furnished with suitable covers.

PART III – EXECUTION

Not applicable.

END OF SECTION

This Page Intentionally Left Blank.