

PART I – GENERAL**WORK SPECIFIED HEREIN**

- All labor, materials, equipment and services necessary to provide prefinished wall panel covering and related items as indicated or specified. **This is a Required Vendor.**

DELIVERY, STORAGE AND HANDLING

- Deliver materials in the original package, containers and bundles bearing the name of the manufacturer and the brand. Store all prefinished panels off the ground under watertight cover and away from any damp surfaces until ready for use. Remove any damaged or deteriorated materials from the site.

SUBMITTALS

- The contractor shall prepare all shop drawings, as required to properly coordinate and construct the project.
- The Contractor shall provide shop drawings with the actual field measured dimensions of all walls to be covered by wall panel covering and trim to the Required Vendor at the time an order is placed. The Contractor assumes all responsibility for the dimensions provided in the shop drawings.
- Review of submittals by the Professional of Record is limited to specific shop drawings as called for in the Project Manual.
- Shop drawings for review by the Professional of Record are not required for this section.

JOB CONDITIONS

- All work herein requires coordination with trades whose work connects with, is affected or concealed by drywall. Before proceeding with the work, make certain all required inspections have been made.
- Inspect surfaces to receive the pre-finished panels before starting work and do not start until surfaces are acceptable. Starting work under this Section implies acceptance of surfaces.

PART II – PRODUCTS**MATERIALS:**

- Wall panel covering and accessories shall be rigid vinyl acrylic .040 inches (1.02mm) nominal thickness, factory finished smooth, color, as indicated on drawings.
- Trim and closure pieces shall be one piece continuous (edges), joint strips, inside and outside corners as required to provide a finished appearance and a water proof installation. All wall panel covering and trim shall be matched for color and texture.
- The wall panel covering and trim accessories shall be purchased from the Required Vendor; and shall be furnished as a complete package system containing all primers and adhesive.

- Primer and adhesive materials shall be water based and non-hazardous.
- The Required Vendor will fabricate the wall panel covering and trim pieces to comply with the requirements of the design, and the dimensions furnished in the shop drawing submittal.
- Refer to Materials and Product Schedule for additional information.

PART III – EXECUTION**INSTALLATION**

- Make preparation to substrate surfaces as required to install panels per the manufacturer's recommendation.
- Apply the adhesive and install the panels and trim per the manufacturer's installation instructions.
- Caulk all seams, edges at walls, curb junctures, penetrations, and corners. Panel installer responsible for all caulking. No button fasteners. Install panels with adhesive as per manufacturer directions.
- Erection techniques shall result in plumb and straight surfaces without waves or buckles, free of unevenness at joints.
- If backing materials are out of alignment, bowed or warped, correct to make true surfaces before application of wall panel covering covers. Use method of correction approved by the Manufacturer. Finished walls shall be made straight, plumb and level without ridges, bows or warps.

WARRANTY

- Materials are to have a 5 year manufacturer's warranty.
- Installation contractor shall not do anything to void the manufacturer's warranty.
- Installation Contractor shall warranty the installation of the system to be water tight for 2 years.

CLEAN - UP

Clean up shall be as per the manufacturer's standards.

DEFECTIVE WORK

All work deemed defective by the Professional of Record shall be corrected as direct by the Professional of Record at no additional cost to the Owner. The following partial list constitutes possible defective work items:

- Non-adhered panels.
- Improperly installed trim.
- Out of plumb and uneven surfaces.
- Damaged panels.

END OF SECTION

This Page Intentionally Left Blank.