

SECTION 10200: LOUVERS AND VENTS

PART I – GENERAL

WORK SPECIFIED HEREIN

- All labor, materials, equipment and services to furnish and install wall louvers as indicated or specified.

SUBMITTALS

- Unless otherwise noted, the contractor shall prepare all shop drawings, product literature, etc. only as required to properly coordinate and construct the project.
- Review of submittals by the Professional of Record is limited to specific shop drawings as called for in the Project Manual.
- Shop drawings for review by the Professional of Record are not required for this section.

SUBSTITUTIONS

- In accordance with Section 01600.

PART II – PRODUCTS

LOUVERS

- Refer to Materials and Product Schedule for Additional Information.
- Stationary rain resistant extruded aluminum louvers. Blades and frames shall be 12 gauge extruded aluminum, alloy 6063-T5. Provide aluminum ½ inch mesh x .063 inch bird screen. Clear anodized finish, 0.7 mil thickness. Louvers shall be completely assembled into sections by factory welding. Furnish 2" flat flange all around exterior face with holes for attachment to wall by expansion bolts.
- Additional louvers as required and specified in other areas of this specification shall be by manufacturers listed above.

PART III – EXECUTION

INSTALLATION

- Install louvers at locations indicated, straight and plumb, in accordance with manufacturer's printed instructions.

END OF SECTION

This Page Intentionally Left Blank.