

PART I – GENERAL**NOTE**

- Refer to Section 15000, General Provisions, Mechanical, which sets forth specific requirements for the mechanical contractors.

SUBMITTALS

- Unless otherwise noted, the contractor shall prepare all shop drawings, product literature, etc. only as required to properly coordinate and construct the project.
- Review of submittals by the Professional of Record is limited to specific shop drawings as called for in the Project Manual.
- Shop drawings for review by the Professional of Record are not required for this section.

WORK INCLUDED

The work required under this division shall consist of all labor, materials, tools, equipment, power, transportation, hoisting implements, services, etc., of every description necessary for the entire completion of the heating, ventilating, and air conditioning work of the contract, all as specified herein and shown on the drawings complete in every respect.

The work in general consists of, but is not necessarily limited to the installation, test, and guarantee of the following work:

- Installation of ductwork according to SMACNA requirements. Connection to the package air-handling units, as manufactured by Lennox.
- Toilet room and miscellaneous exhaust systems.
- Weather seals at A/C unit curbs.
- Smoke Detectors at ductwork.
- Grilles, registers, ceiling outlets, louvers, dampers, and access doors.
- Insulation (Internal and External)
- Tests, balances, and adjustment.
- All special supports, other than concrete, required for HVAC equipment, furnished by the mechanical contractor.
- All other miscellaneous items of equipment, materials and ductwork, as hereinafter specified, as shown on the drawings, or as required for the proper completion and operation of the heating, ventilating, and air conditioning system.

REGULATIONS, PERMITS AND INSPECTIONS

- Regulations: All materials, equipment, and installation shall comply with all applicable codes, rules and regulations, all of which shall be considered a part of these specifications.
- Inspections: When required by code, all work shall be inspected and approved by local authorities. Prior to final review by architect, furnish Professional of Record with certificates of inspections and approvals by the local authorities, as per Section 01700.

END OF SECTION

This Page Intentionally Left Blank.